



NOTES

1. FOR NON STREET TREE PLANTINGS CONSIDER USE OF SPACE, PEDESTRIAN ACCESS, ROOTS, LIGHTING AND SERVICES. WHEN POSITIONING TREES REFER TO LANDSCAPING PLAN FOR THE LOCATION.
2. MINIMUM 25 LITRE CONTAINER-ADVANCED PLANT STOCK OR AS SPECIFIED ON APPROVED PLAN.
3. EXCAVATED PLANTING HOLE TO ALLOW CLEARANCE AROUND ROOTBALL. RIP BASE OF HOLE TO 150mm DEPTH TO PROMOTE DRAINAGE. BACKFILL WITH GOOD TOPSOIL AND 2 No AGRIFORM TABLETS, OR SIMILAR. ENSURE TOP OF ROOTBALL IS INSTALLED FLUSH WITH EXISTING GROUND LEVEL. MOULD EXCAVATED SOIL INTO 1.0m DIAMETER CIRCLE TO CREATE "SAUCER". INSTALL 100mm DEPTH MULCH IN A 1.0m DIAMETER CIRCLE (MINIMUM) AROUND THE BASE OF THE TREE. SECURE TREE TO 38 X 38 X 1.8m HARDWOOD STAKES WITH RUBBER OR HESSIAN TIES. THOROUGHLY WATER TREE AFTER PLATING.
4. THE GOOD QUALITY TOPSOIL SPECIFIED FOR BACKFILLING PLANTING PITS, SHALL BE IMPORTED FROM AN APPROVED SOURCE. IT SHALL BE NATURAL, FRIABLE, SANDY LOAM, WITHOUT A CLAY BASE AND CONTAINING HUMUS. PH SHALL BE BETWEEN 5.5 - 7.0. TOPSOIL SHALL BE FREE FROM ROCK, STICKS, WEEDS, SALT ETC. AND SHALL BE CAPABLE OF SUSTAINING HEALTHY PLANT GROWTH.
5. MULCH SHALL BE AGED WOODCHIP OR SIMILAR, STOCKPILED FOR A MINIMUM OF SIX WEEKS. IT SHALL BE FREE OF ROCKS, NON BIO-DEGRADABLE AND TOXIC MATERIAL.
6. FOR SUITABLE TREES SEE POLICY 120 OR AS SPECIFIED IN APPROVED LANDSCAPE PLAN.

Armidale <i>Dept of Public Regional Council Infrastructure</i>	SCALES NTS	APPROVED D. MAUNDER 10/11/2016 <small>MANAGER ENGINEERING AND STANDARDS SUPPORT</small>	DATE	SHEET 1 OF 1
		SURV DRWN GW DES CHKD MW	AS SHEET SIZE A3	DRAWING No 030-082
TYPICAL NON STREET TREE PLANTING WITHOUT ROOT GUARD		CADFILE 030-082.dwg		DATE 10/11/2016